

90.2(B)(5) d.

٢

- c. Are located in legally established easements or rightsof-way, or
- d. Are located by other written agreements either designated by or recognized by public service commissions, utility commissions, or other regulatory agencies having jurisdiction for such installations.

NECA


NECA




90.2(B)(5) d. [cont'd.]

- These installations shall be limited to:
- Federal lands, native American reservations through the U.S. Department of the Interior Bureau of Indian Affairs,
- Military bases, lands controlled by port authorities
- State agencies and departments, and lands owned by railroads.

6










Associate and revised Relocated and revised The connection between the grounded circuit conductor and the supply-side bonding jumper, or the equipment grounding conductor, or both, at a separately derived system.


NECA

























































٢	
	Section 240.87 [new]
	This new section addresses non-instantaneous trip circuit breakers operating characteristics and methods to reduce energy levels when equipment has to be worked on, tested, inspected, or maintained while energized.
	The three methods are provided to reduce energy levels.
28	NËCA




240.91(B) Device Rated Over 800 Amperes

- Permits conductors in circuits over 800 amperes to have overcurrent protection applied above their rated capacity.
- Applies to equipment listed and marked for this use where conductors are protected within the time/current conductor withstand ratings.
- Applies only in supervised industrial installations


30































٢	250 101 Crosur dia a Sustan
	250.191 Grounding System at AC Substations
	 For ac substations, the grounding system shall be in
	accordance with Part III of Article 250.
	• Informational Note: For further information on outdoor ac substation grounding, see ANSI/IEEE 80-2000, IEEE <i>Guide for Safety in AC Substation Grounding.</i>
40	NËCA





















Article 399 [New]

e

48


This new article provides the requirements for overhead conductors outside that are installed for systems operating at over 600 volts.


Many overhead electrical infrastructures operating over 600 volts are customer-owned and outside of the control of serving utility companies.


The *NEC* has been expanded to provide new rules that apply to overhead conductor installations.


















٢	
	406.4(D) [Revision] (cont.)
	(6) Receptacle replacements made at outlets that require
	weather-resistant receptacles, the receptacles must be of the weather-resistant type.
55	NËCÆ




Section 406.11 [Revision]


The requirements for tamper-resistant receptacles have been expanded beyond dwelling units.


A new subdivision (B) has been added that requires tamper-resistant receptacles in all public areas where children are predominately present, such as daycares, classrooms, churches, restaurants, restrooms, bathrooms, playrooms, activity rooms, playgrounds, swimming pools, and as described in 517.18 (C).

57



NECA





Section 408.3(F) (2) [New] This revision incorporates a new requirement to field-mark switchboards and panelboards that are supplied by ungrounded systems (sources). The new rule includes specific language that must be used on the labels that warn users of the ungrounded system and what the operating voltage is. The label has to include the following wording: Caution Ungrounded System Operating _____ Volts Between Conductors

NECA



Section 408.4 [Revision]

This section has been revised by adding a new subdivision (B) that requires each switchboard or panelboard to be field-marked as to where the power supplying the equipment originates.


The title of this section has also been changed from "Signage" to "Field Identification Required."


63

e















































































Installation by Qualified Persons 690.4(E), 692.4(C), 694.7, 705.6 [qualified persons] The equipment and systems in 690.4(A) through (D) and all associated wiring and interconnections shall be installed only by qualified persons.

• Informational Note: See Article 100 for the definition of *qualified person.*


88














690.11 Arc-Fault Circuit Protection (Direct Current)

٢


94


• Photovoltaic systems with dc source circuits, dc output circuits, or both, on or penetrating a building operating at a PV system maximum system voltage of 80 volts or greater, shall be protected by a listed (dc) arc-fault circuit interrupter, PV type, or other system components listed to provide equivalent protection.







Article 694 [New] This article applies to small wind electric systems (also known as small wind turbine systems) The new article includes associated equipment such as generators, alternators, inverter(s), and controller(s) for such systems.






Additional content of the end o











Article 800 Informational Note

- The term grounding conductor has been replaced by either the term *grounding electrode conductor* or *bonding conductor*.
- Two new figures show the conductors of grounding and bonding systems for communications systems installations.

105

0

